

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS
COASTAL RESOURCES MANAGEMENT COUNCIL
Oliver Stedman Government Center
4808 Tower Hill Road, Wakefield, RI 02879

PUBLIC NOTICE

File Number: 2009-11-003 Date: November 4, 2009

This office has under consideration the application of:

Linda Oliver Hughes
232 Indian Trail
Saunderstown, RI 02874

for a State of Rhode Island Assent to construct and maintain a residential boating facility to replace a previous assented residential boating facility. The proposed facility is to consist of a 4' wide by 30' long fixed structure that leads to a 3' x 15' ramp that leads to a 150 s.f. terminal float. The proposed structure is to extend 41 feet seaward of the cited Mean Low Water mark.

Project Location:	232 Indian Trail
City/Town:	Narragansett
Plat/Lot:	NK / 1-3
Waterway:	Narrow River

Plans of the proposed work may be seen at the CRMC office in Wakefield.

In accordance with the Administrative Procedures Act (Chapter 42-35 of the Rhode Island General Laws) you may request a hearing on this matter.


You are advised that if you have good reason to enter protests against the proposed work it is your privilege to do so. It is expected that objectors will review the application and plans thoroughly, visit site of proposed work if necessary, to familiarize themselves with the conditions and cite what law or laws, if any, would in their opinion be violated by the work proposed.

If you desire to protest, you must attend the scheduled hearing and give sworn testimony. A notice of the time and place of such hearing will be furnished you as soon as possible after receipt of your request for hearing. If you desire to request a hearing, to receive consideration, it should be in writing and be received at this office on or before December 4, 2009.

/lam

Pettaquamscutt River
(Narrow River)
Type 2 Water

Bench Mark
CORNER OF CONC. PAD
ELEVATION=21.66
(MEAN SEA LEVEL)



NO S.A.V.'S OBSERVED

Site Plan

GRAPHIC SCALE



(IN FEET)
1 inch = 20 ft.

DOCK APPLICATION
FOR
Linda Hughes
232 Indian Trail,
In The Town Of Narragansett
Map N-K, Lot 1-3

Date: 11/2/09

Job Number: 6633001

WESLEY GRANT III

No. 3157


REGISTERED
PROFESSIONAL ENGINEER

ENVIRONMENTAL PLANNING & SURVEYING, INC.



Civil Engineering
Surveying
C A D Drafting

22 Kersey Road, Wakefield, Rhode Island 02879 (401) 789-3628



Elevation


Scale: 1"=15'

DOCK APPLICATION

FOR
 Linda Hughes
 232 Indian Trail,
 In The Town Of Narragansett
 Map N-K, Lot 1-3

Date: 11/2/09

Job Number: 6633001




ENVIRONMENTAL PLANNING & SURVEYING, INC.



Civil Engineering
 Surveying
 C A D Drafting

22 Kersey Road, Wakefield, Rhode Island 02879 (401) 789-3628



NOTES:
 STRINGERS SHALL BE BOLTED THRU PILES
 ALL NAILS TO BE 12d GALVINIZED
 PILE PENETRATION 10' (MIN.)

NOTE: HOT DIPPED GALVANIZED (OR STAINLESS STEEL) FASTENERS SHALL BE USED AS REQUIRED.


Section View

DOCK APPLICATION

FOR
 Linda Hughes
 232 Indian Trail,
 In The Town Of Narragansett
 Map N-K, Lot 1-3

Date: 11/2/09

Job Number: 6633001






ENVIRONMENTAL PLANNING & SURVEYING, INC.



Civil Engineering
 Surveying
 C A D Drafting

22 Kersey Road, Wakefield, Rhode Island 02879 (401) 789-3628



RAMP DETAILS

NO SCALE


NOTE: HOT DIPPED GALVANIZED (OR STAINLESS STEEL) FASTENERS SHALL BE USED AS REQUIRED.

DOCK APPLICATION

FOR
 Linda Hughes
 232 Indian Trail,
 In The Town Of Narragansett
 Map N-K, Lot 1-3

Date: 11/2/09

Job Number: 6633001




ENVIRONMENTAL PLANNING & SURVEYING, INC.




Civil Engineering
 Surveying
 C A D Drafting


22 Kersey Road, Wakefield, Rhode Island 02879 (401) 789-3628



PLAN



NOTE: USE PVC PIPE AS ROLLERS WITH CHAIN TYPE PILE HOLDERS TO MINIMIZE ABRASION.




NOTE: HOT DIPPED GALVANIZED (OR STAINLESS STEEL) FASTENERS SHALL BE USED AS REQUIRED.

DOCK APPLICATION

FOR
Linda Hughes
232 Indian Trail,
In The Town Of Narragansett
Map N-K, Lot 1-3

Date: 11/2/09

Job Number: 6633001



ENVIRONMENTAL PLANNING & SURVEYING, INC.



Civil Engineering
Surveying
C A D Drafting

22 Kersey Road, Wakefield, Rhode Island 02879 (401) 789-3628

GENERAL SPECIFICATIONS

GENERAL

THE PROPOSED DOCK IS LOCATED IN TYPE 2 WATERS AS DESIGNATED BY THE RHODE ISLAND COASTAL RESOURCES MANAGEMENT COUNCIL.

NO MORE THAN FOUR BOATS ARE PERMITTED TO USE THE PROPOSED DOCK AT ONCE

STRUCTURAL

DESIGNED PEDESTRIAN LIVE LOAD:

FIXED PIER = 40 P.S.F. (10 PSF DEAD LOAD)

FLOATS = 20 P.S.F. OR 400 LBS. CONCENTRATED.

MATERIALS

WOOD

ALL WOOD IS TO BE SOUTHERN YELLOW PINE, PRESSURE TREATED WITH TYPE III CHROMATED COPPER ARSENATE (CCA) TO THE FOLLOWING DENSITIES:

DECKING: .4 POUNDS PER CUBIC FOOT (PCF)

PILES: 1.0 - 1.5 PCF

ALL OTHERS: .6 PCF

HARDWARE

ALL HARDWARE IS TO BE HOT DIPPED GALVANIZED.

PILINGS

THE PILINGS ARE TO BE 8" MINIMUM TIP DIAMETER AND ARE TO BE DRIVEN TO A MINIMUM DEPTH OF 10' BELOW BOTTOM SEDIMENTS. IF REFUSAL IS ENCOUNTERED BEFORE THE PILING IS DRIVEN TO THE SPECIFIED DEPTH. THE CONTRACTOR IS TO DETERMINE IF THE PILING IS ADEQUATELY SUPPORTED OR SHOULD BE RELOCATED TO ACHIEVE A DEEPER PENETRATION.

DOCK APPLICATION

FOR
Linda Hughes
232 Indian Trail,
In The Town Of Narragansett
Map N-K, Lot 1-3

Date: 11/2/09

Job Number: 6633001

WESLEY GRANT III

No. 3157

REGISTERED
PROFESSIONAL ENGINEER

ENVIRONMENTAL PLANNING & SURVEYING, INC.



Civil Engineering
Surveying
C A D Drafting

22 Kersey Road, Wakefield Rhode Island 02879 (401) 789-3628