

State of Rhode Island Coastal Resources Management Council Oliver H. Stedman Government Center 4808 Tower Hill Road, Suite 3 Wakefield, RI 02879-1900

(401) 783-3370 Fax (401) 783-2069

# **PUBLIC NOTICE**

File Number: 2022-06-032 Date: September 27, 2022		
---	--	--

This office has under consideration the application of:

Safe Harbor Allen Harbor 14785 Preston Road Suite 975 Dallas, TX 75254

for a State of Rhode Island Assent to construct and maintain: A negative lift. This negative lift will include a 40 ft +/- steel sheet pile bulkhead with a deadman anchoring system and concrete cap, 62 ft +/- of cantilevered steel sheet pile bulkhead with a concrete cap, an  $1,100 \text{ft}^2$  concrete platform, a new 20 ft gangway,  $950 \text{ft}^2$  +/- of new floats, 13 new 12 " timber piles, regrading of the shoreline and upland area, and the addition of a vessel well.

	84 Wescott Road
Project Location:	
City/Town:	North Kingstown
Plat/Lot:	194 / 19
Waterway:	Allen Harbor

Plans of the proposed work can be requested at <a href="Cstaffl@crmc.ri.gov">Cstaffl@crmc.ri.gov</a>.

In accordance with the Administrative Procedures Act (Chapter 42-35 of the Rhode Island General Laws) you may request a hearing on this matter.

You are advised that if you have good reason to enter protests against the proposed work it is your privilege to do so. It is expected that objectors will review the application and plans thoroughly, visit site of proposed work if necessary, to familiarize themselves with the conditions and cite what law or laws, if any, would in their opinion be violated by the work proposed.

If you desire to protest, you must attend the scheduled hearing and give sworn testimony. A notice of the time and place of such hearing will be furnished you as soon as possible after receipt of your request for hearing. If you desire to request a hearing, to receive consideration, it should be in writing (with your correct mailing address, e-mail address and valid contact number) and be received at this office on or before October 27, 2022.

Please email your comments/hearing requests to: <a href="mailto:cstaff1@crmc.ri.gov">cstaff1@crmc.ri.gov</a>; or mail via USPS to: Coastal Resources Management Council; O. S. Government Center, 4808 Tower Hill Road, Rm 116; Wakefield, RI 02879.

CRMC Mailing List for Safe Harbor Allen Harbor CRMC File Number 2022-06-032

Safe Harbor Allen Harbor 14785 Preston Road Suite 975 Dallas, TX 75254

CRMC (2022-06-032) O. S. Government Center 4808 Tower Hill Road Wakefield, RI 02879

Quonset Davisville Navy Yacht Club P.O. Box 641 North Kingstown, RI 02852

United States of America C/O EDC 95 Cripe Street North Kingstown, RI 02852

General List/NK List

# SAFE HARBOR MARINAS ALLEN HARBOR

DRAWING LIST		
DRAWING No.	DRAWING TITLE	
1	TITLE SHEET & GENERAL NOTES	
2	VICINITY MAP	
3	AERIAL IMAGE	
4	EXISTING SITE PLAN	
5	EXISTING PARTIAL PLAN	
6	PROPOSED SITE PLAN	
7	PROPOSED PARTIAL PLAN	
8	SECTION A-A	
9	SECTION B-B	
10	SECTION C-C	
11	SEDIMENTATION & EROSION CONTROLS	

#### **GENERAL NOTES**

- THE PURPOSE OF THESE DRAWINGS ARE FOR REGULATORY REVIEW ONLY.
- 2. VICINITY MAP TAKEN FROM USGS.
- 3. ELEVATIONS REFERENCE NAVD 88, UNLESS NOTED OTHERWISE.
- 4. THIS SITE INFORMATION HAS BEEN TAKEN FROM A DRAWING TITLED "2021 ALTA/NSPS LAND TITLE SURVEY", PREPARED FOR SAFE HARBOR MARINAS, LLC, BY CONTROL POINTS ASSOCIATES, INC., DATED 05/20/2021, AND REVISED ON 07/01/2021.
- 5. SUPPLEMENTARY INFORMATION OBTAINED BY RACE COASTAL ENGINEERING, LLC ON 10/22/2021 AND ONLY REPRESENT THE SITE CONDITIONS AT THAT TIME.

THE TIDAL DATA SHOWN WAS TAKEN FROMTHE U.S. DEPARTMENT COMMERCE, NATIONAL OCEANIC AND ATMOSPHERIC AMBINISTRATION (NOAA) ONLINE VERITCAL DATUM PANSFORMATION PROGRAM, DETERMINED AT THE FOLLOWING CATION:

LOCATION: QUONSET, RHODE ISLAND


LATITUDE: 41.614 N LONGITUDE: 71.405 W


 REFERENCE TO QVD WAS OBTAINED FROM A PLAN TITLED "SURVEY CONTROL PLAN FOR RHODE ISLAND ECONOMIC DEVELOPMENT CORPORATION" PREPARED BY FOSTER SURVEY COMPANY OF WARWICK, RI AND LAST REVISED JULY 23, 2008.

PROJECT TIDAL ELEVATIONS:			
DATUM	NAVD 88 (FT)	MLW (FT)	QVD (FT)
MEAN HIGHER HIGH WATER (MHHW)	+1.88'	+4.06'	+4.93
MEAN HIGH WATER (MHW)	+1.63'	+3.81'	+4.68'
NAVD 88	0.00	+2.18'	+3.05'
MEAN LOW WATER (MLW)	-2.18'	0.00	+0.87'
MEAN LOWER LOW WATER (MLLW)	-2.33'	-0.15'	+0.72'
QVD	-3.05	-0.87'	0.0

	Prepared For:	r
	SAFE HARBOR MARINAS	ı
	ALLEN HARBOR	ı
	84 WESTCOTT ROAD	ı
IVACL	NORTH KINGSTON, RI 02852	١
COASTAL ENGINEERING	Project: MARINA IMPROVEMENTS	Ī
611 Access Road Stratford, CT 06615	84 WESCOTT ROAD (PLAT 194, LOT 19)	ı
Tel: 203-377-0663 racecoastal.com	NORTH KINGSTON, RI 02852	١
ALL RIGHTS RESERVED.	NOT FOR CONSTRUCTION	N
©2020 RACE COASTAL ENGINEERING, LLC. FOR REGULATORY REVIEW ON		







# **AERIAL MAP**



611 Access Road Stratford, CT 06615 Tel: 203-377-0663 racecoastal.com Prepared For: SAFE HARBOR MARINAS **ALLEN HARBOR** 

**84 WESTCOTT ROAD** NORTH KINGSTON, RI 02852

Project: MARINA IMPROVEMENTS 84 WESCOTT ROAD (PLAT 194, LOT 19) NORTH KINGSTON, RI 02852

ALL RIGHTS RESERVED. ©2020 RACE COASTAL ENGINEERING, LLC. NOT FOR CONSTRUCTION FOR REGULATORY REVIEW ONLY



Date:	Rev. #3:
02-07-2022	05-19-2022
Drawn By:	Checked By:


MJW/ZMV MRR


Datum: Scale:


NAVD88 1"=600" Project No.: Drawing No.:


3 of 11


2021118 NOT VALID WITHOUT ENGINEER'S SEAF

















- CURTAIN AND ANCHOR MUST RESIST EXPECTED WIND, WAVE AND CURRENT ENVIRONMENT AT SITE. CONTRACTOR TO SUBMIT PROPOSED WEIGHTED TURBIDITY CURTAIN SPECIFICATIONS FOR REVIEW/APPROVAL.
- WORK IS ANTICIPATED TO BE COMPLETED IN SECTIONS. THE CONTRACTOR SHALL CONFINE THE WORK
  AREA WITH SEDIMENTATION AND EROSION CONTROL MEASURES AS NECESSARY TO COMPLETE THE
  WORK AND IN ACCORDANCE WITH REGULATORY AUTHORIZATIONS.

#### S&E NOTES:

Ш


- LAND DISTURBANCE SHALL BE KEPT TO A MINIMUM.
- PRIOR TO START OF WORK CONTRACTOR SHALL INSTALL APPROPRIATE, S&E CONTROL MEASURES SHALL BE INSTALLED.
- 3. CONTRACTOR SHALL IMMEDIATELY REPAIR
  ANY BEACHES OR DAMAGES TO S&E
  CONTROLS. S&E CONTROLS SHALL BE
  NAINTAINED THROUGHOUT CONSTRUCTION
  AND REPLACED AS REQUIRED TO ASSURE
  S&E CONTROLS ARE OPERATING
  DEFFECTIVELY.

ADDITIONAL CONTROL MEASURES SHALL BE UNIVERSE SHALL BE UNIVERSE SHALL BE UNIVERSE SHALL BE UNIVERSE.

5. THE CONTRACTOR SHALL UTILIZE APPROVED METHODS/MATERIALS FOR PREVENTING THE BLOWING AND MOVEMENT OF DUST FROM EXPOSED SOIL SURFACES ONTO ADJACENT PROPERTIES AND SITE AREAS.

# S&E NOTES (CONT.):

 THE CONTRACTOR SHALL MAINTAIN AN ADDITIONAL SUPPLY OF EROSION & SEDIMENTATION CONTROL ON SITE FOR EMERGENCY PURPOSES.



# HAY BALES

### NOTE(S):

 INSTALL HAY BALES ALONG ENTIRE PERIMETER OF SOIL STOCKPILE LOCATION(S).

