(401) 783-3370 Fax (401) 783-2069

PUBLIC NOTICE

File Number:	2021-08-044	Date:	September 9, 2021
This office has	under consideration the application of:		

Steven & Colleen Carr 20 Tristan Ct. Smithfield, RI 02917

for a State of Rhode Island Assent to construct and maintain: A \sim 98' residential boating facility consisting of a 4' x 66' fixed timber pier, 4' x 26 ramp and 8' x 18.75' (150sf) terminal float. The facility is proposed to extend \sim 53' seaward of the cited MLW mark, requiring a 3' length variance to Red Book 650-RICR-20-00-01 Section 1.3.1(D)(11)(1).


Project Location:	31 Sunset Shore Drive
City/Town:	Narragansett
Plat/Lot:	R-1 / 172
Waterway:	Point Judith Pond, Bluff Hill Cove, Type II

Plans of the proposed work may be seen at the CRMC office in Wakefield.

In accordance with the Administrative Procedures Act (Chapter 42-35 of the Rhode Island General Laws) you may request a hearing on this matter.


You are advised that if you have good reason to enter protests against the proposed work it is your privilege to do so. It is expected that objectors will review the application and plans thoroughly, visit site of proposed work if necessary, to familiarize themselves with the conditions and cite what law or laws, if any, would in their opinion be violated by the work proposed.


If you desire to protest, you must attend the scheduled hearing and give sworn testimony. A notice of the time and place of such hearing will be furnished you as soon as possible after receipt of your request for hearing. If you desire to request a hearing, to receive consideration, it should be in writing (with your correct mailing address, e-mail address and valid contact number) and be received at this office on or before October 9, 2021.




PROPOSED RESIDENTIAL PIER FOR STEVEN & COLLEEN CARR 31 SUNSET SHORE DRIVE AP R-1, LOT 172 NARRAGANSETT, RI 02882 BY: WARREN HALL, CIVIL ENGINEER JULY 23, 2021 SHEET 1 OF 4










PILE DRIVING NOTE:


A "soft start" is required to allow animals an opportunity to leave the project vicinity before sound pressure levels increase. In addition to using a soft start at the beginning of the work day for pile driving, one must also be used at any time following cessation of pile driving for a period of 30 minutes or longer. For impact pile driving: pile driving will commence with an initial set of three strikes by the hammer at 40% energy, followed by a one minute wait period, then two subsequent 3-strike sets at 40 with one minute waiting periods, before initiating continuous impact driving.




- 10" TIP CCA TREATED WOOD PILES
 TREAT TO 2.5 PCF (1.0 ALLOWED WITH
 OWNER CONSENT) GREENHEART AT FLOAT
- (2) 2x6 DECKING ACQ TREATED TO .6 PCF FASTEN TO STRINGERS WITH 3 @ 3-1/2" NO. 10 316 STAINLESS STEEL SCREWS
- 3x12 STRINGER, ACQ TREATED THRU BOLT AT PILE FASTEN MIDDLE STRINGER WITH SIMPSON H-1 HURRICANE ANCHOR
- 4 2-3x12 CAP BEAM, ACQ TREATED TO .6 PCF
- (3) 3x10 CROSS BRACE, ACQ TREATED TO 2.5 PCF

GENERAL NOTES:

- 1) ALL BOLTS, CONNECTORS, WASHERS, NAILS, ECT SHALL BE HOT DIPPED GALVANIZED
- 2) CONTRACTOR SHALL ADHERE TO ALL OSHA RULES AND REGULATIONS THROUGHOUT ALL PHASES OF CONSTRUCTION
- 3) CONTRACTOR SHALL BE AWARE THAT THE STRATA INTO WHICH THESE PILES ARE TO BE DRIVEN MAY REQUIRE DRILLING TO ENSURE A MINIMUM 10' PENETRATION BELOW EXISTING GRADE





PROPOSED REIDENTIAL PIER FOR STEPHEN CARR 31 SUNSET SHORE DRIVE AP R-1, LOT 172 NARRAGANSETT, RI 02879 BY: WARREN HALL CIVIL ENGINEER MAY 3, 2021 PAGE 4 OF 4



